

Table 1. Composited assay results for Phase 1 drilling of the Cowboy Zone, LDI Mine

Drill Hole	Section	From (m)	To (m)	Length (m)*	Pd g/t	Pt g/t	Au g/t	Cu%	Ni%	Co%
09-102	504N	340	345	5	3.26	0.36	0.12	pending	pending	pending
09-103	504N	387	392	5	3.28	0.36	0.07	0.032	0.073	0.005
09-104	504N	453	460	7	3.22	0.35	0.16	0.049	0.083	0.006
09-105	503N	503	507	4	5.10	0.41	0.19	0.190	0.145	0.010
09-106	503N	535	543	8	4.70	0.36	0.32	0.173	0.135	0.007
09-108	503N	484	492	8	2.37	0.24	0.04	0.016	0.040	0.004
09-112	503N	549	556	7	3.94	0.53	0.15	0.029	0.063	0.005
09-120	502N	511	515	4	3.88	0.47	0.77	0.150	0.141	0.008
09-202	501N	502	508	6	3.57	0.43	0.30	0.192	0.145	0.007
09-202	501N	519	524	5	4.46	0.56	0.46	0.241	0.184	0.008
09-204	501N	506	522	16	3.58	0.37	0.14	0.094	0.119	0.007
including	501N	507	518	11	4.21	0.43	0.15	0.100	0.131	0.007
09-205	501N	560	568	8	2.42	0.29	0.16	0.076	0.070	0.005
09-209	500N	459	469	10	2.53	0.30	0.27	0.088	0.096	0.006
09-211	500N	578	582	4	3.00	0.30	0.16	0.121	0.117	0.008
09-217	499N	479	489	10	2.33	0.26	0.11	0.060	0.068	0.004
including	499N	483	488	5	3.05	0.34	0.15	0.081	0.088	0.005
09-218	499N	540	555	15	3.21	0.35	0.15	0.109	0.120	0.006
including	499N	540	549	9	3.63	0.40	0.14	0.108	0.126	0.006
Notes:										
*Minimum 4 metre length										
Hole lengths expected to be within 70-80% of true widths										